

INDUSTRIAL SERVICES

500 HARVARD DRIVE - BELLE RIVER - ONTARIO - NOR 1A0 - (519) 727-3713 - info@lekter.net

Dec 17, 2019

Town of Tecumseh
Tecumseh ON

Attention: Kirby McArdle

Subject: pump repair at St Mark Storm water Station

Based on discussion with Jay Harris and Cascade pump Co. our scope of work is as follows;

On site disconnect & removal of cascade pump and motor via crane, Deliver to MDR shop, dis-assemble, visual assessment of components, replace Bowl Assembly. This a similar bowl assembly to that supplied originally, model #14AP for St. Clair Beach. It includes a stainless steel liner, a galvanized basket strainer and standard black enamel paint. Re-assemble pump with new lower assembly and prep for shipment.

Motor work - Dis-assembly - AWA windings, also visual inspection, check all fits, clean all parts Wash & Bake stator, replace bearings, Glyptal winding, Re-assemble & test, paint.

NOTE: If we find any other anomalies or wear with pump not visible, (ie..shaft deterioration,) an additional quote will be provided prior to work performed. Any Mechanical/machining work required on Motor would be extra.

Deliver & Crane pump assembly back into position, re-mount motor and align, replace dresser coupling, secure assembly and commission startup & run

Price \$ 26,433.00 Delivery 6-8 weeks from receipt of order Taxes are extra, valid for 30 days

Thank you for the opportunity to quote your project. Please call at your convenience if you have any questions.

Respectfully submitted

Roger Rivard (Sales Mgr)